WASTE FACILITY PERMIT

Issued by Meath County Council

comhairle chontae na mí
meath county council

Issued under the Waste Management Act 1996, as amended,
Waste Management (Facility Permit & Registration) Regulations 2007, as amended

Waste Facility Permit Number:	**WFP-MH-20-0008-02**
Issued to:	**Great White Destruction** **Units 2A-2B Enterprise Centre,** **Summerhill,** **Co. Meath**
Location of Facility:	**Units 2A-2B Enterprise Centre,** **Summerhill,** **Co. Meath** **A83 AW66**
Grid Reference of Facility: **(Nominal centre point)**	**X (ITM) 684497** **Y (ITM) 749030**
Permit Holder Contact Details :	**David Walsh (046-9557508)**
Date Granted:	**24th November 2025**
Date of Expiry:	**23rd November 2030**
Environment Order Number:	**30951/2025**

Signed: _____ **Date:** 24/11/2025

Kitty Foyle
Senior Executive Officer

NOTE 1: The permit holder may appeal the conditions, attached to this waste facility permit, to a court of competent jurisdiction

NOTE 2: Should the permit holder wish to continue to operate after the date of expiry, an application to review the waste facility permit shall be made to Meath County Council in accordance with Article 31 (1) of the Regulations no later than 60 working days before the date of expiry of this waste facility permit

NOTE 3: Should the permit holder not wish to continue waste activities at any time or after the date of expiry of this waste facility permit, the permit holder shall by notice in writing apply to Meath County Council for the surrender of the waste facility permit in accordance with Article 29 of the Regulations.

INTERPRETATION

Unless otherwise specified, all terms in this waste facility permit should be interpreted in accordance with the definitions in the Waste Management Act 1996 (the Act) and its associated Regulations, or the European Communities Act and its associated Regulations or as defined in this waste facility permit.

References to any enactment, statutory instrument (including any bye-law), each as defined by the Interpretation Act 2005, or a regulation, directive or decision of a European Union institution in this permit shall include amendments and replacements.

The granting of this Waste Facility Permit, and any condition imposed by it, does not exempt the holder of the Waste Facility Permit with complying with the statutory obligations of any relevant legislation, including Water Pollution, Air Pollution, Waste, Litter and Planning Legislation or legal liabilities under any other enactment or regulations whatsoever. The permit holder is legally responsible for all aspects of the operation and management of the permitted activity.

INTRODUCTION

This introduction is not part of the waste facility permit and does not purport to be a legal interpretation of the waste facility permit.

- The proposed activity is for the importation of a variety of paper wastes, redundant office & IT equipment & WEEE within the landholding at Units 2A & 2B Enterprise Centre, Summerhill, Co. Meath.
- All cardboard, paper and plastics are shredded baled and exported to UK & Europe using a registered broker. Annex VII are completed for each load shipped overseas.
- The maximum tonnes brought in per year will be 6,500 tonnes per year.

TABLE OF CONTENTS:

Part 1: Waste Activities Permitted 5
PART 2: CONDITIONs 1.0 SCOPE 7
2.0 Management of the Activity 9
3.0 Notification & Record Keeping 12
3.1 Waste Register/Records 12
3.2 Incident Reporting & Complaints Register 13
3.3 Annual Report 14
4.0 Site Access & Infrastructure 17
4.1 Facility Notice Board 17
4.2 Tank, Container & Drum storage area 17
4.3 Facility Security 18
4.4 Facility Roads & Surfaces 18
4.5 Facility Office 18
4.6 Waste Inspection and Quarantine 18
4.7 Storm Water 19
4.8 Waste Handling, Ventilation and Processing Plant 19
5.0 Waste Acceptance & Handling 21
5.1 Waste Acceptance 21
6.0 ENVIRONMENTAL MONITORING 22
6.1 Environmental Monitoring 22
6.2 Discharge to Surface Water 22
6.3 Noise 22
7.0 Nuisances, Emissions & Environmental Impact 23
7.1 Environmental Protection 23
7.2 Noise/Odour/Dust/Nuisances 23
7.3 Litter 24
7.4 Pests 24
8.0 Contingency Arrangements 25
9.0 Charges & Financial Provisions 26
9.1 Fees 26
9.2 Financial Provisions 26
10.0 Restoration & Aftercare 28
10.1 Closure, Restoration & Aftercare Management Plan (CRAMP) 28

11.0 Changes to permit holder status & cessation of waste activities..... 29
11.1 Changes to permit holder status: 29
11.2 Cessation of waste activities:..... 29
APPENDICES..... 31
Appendix A: 31
APPENDIX A.1. – PERMITTED WASTE TONNAGE..... 31
Appendix A.2 – Waste acceptance 31
Appendix B- Waste Register 33
Appendix C – Incident Register 34
Appendix D – Complaints Register..... 35
Appendix E - Environmental Monitoring..... 36
Appendix F - ARTICLE 21 WASTE MANAGEMENT (WEEE) REGULATIONS..... 37
Appendix G - Site maps..... 38

PART 1: WASTE ACTIVITIES PERMITTED

The permitted classes of activities, in accordance with Part I of the Third Schedule of the Waste Management (Facility Permit & Registration) Regulations, 2007 as amended:

Class	Description
Principal Class: 10	The recovery of waste (not mentioned elsewhere in this part of the third schedule), other than hazardous waste, or an activity specified in Category 5 of Annex 1 of Directive 2010/75/EU, where – (a). the annual intake does not exceed 50,000 tonnes, and (b). the maximum quantity of the residual waste consigned from the facility for onward transport and submission to disposal at an authorized facility shall not exceed 15% of the annual intake.
Class 1	The reception and temporary storage, pending collection, other than by local authority, where not otherwise regulated by a waste licence or certificate of registration, or exempted in accordance with the provisions of article 39 of the Waste Management (Waste Electrical and Electronic Equipment) Regulations 2005 of – 1) Household hazardous waste (other than WEEE and mercury containing waste or used batteries and accumulators) at a civic amenity facility, recycling centre or central collection point where annual intake shall not exceed – i. In the case of liquid waste, 100,000 litres ii. In the case of non-liquid waste, 100 tonnes 2) WEEE at any premised for the purpose of onward transport and submission to recovery at an authorised facility.
Class 3	The reception treatment and recovery of WEEE (including removal of all fluids and dismantling or disassembly or removal of WEEE substances, preparations and components prior to treatment) in accordance with the provisions of articles 20 & 21 of the Waste Management (WEEE) Regulations (S.I. No 240 of 2005) Annual intake shall not exceed 10,000 tonnes per annum.
Class 4	The reception, storage and recovery of scrap metal, including scrap metal arising from end-of-life vehicles, waste vehicles (other than end-of-life vehicles) and WEEE where scrap metal from — (1) end-of-life vehicles shall be subject to appropriate treatment and recovery in accordance with the provisions of articles 14 and 15 of the Waste Management (End-of-Life Vehicles) Regulations 2006 (S.I. No. 282 of 2006) prior to acceptance at the scrap metal facility, and as appropriate, (2) waste vehicles (other than end-of-life vehicles) shall be subject to appropriate treatment and recovery having regard to the provisions of articles 14 and 15 of the Waste Management (End-of-Life Vehicles) Regulations 2006 (S.I. No. 282 of 2006) prior to acceptance at the scrap metal facility, and as appropriate, (3) WEEE shall be subject to appropriate treatment and recovery in accordance with the provisions of articles 20, 21 and 22 of the Waste Management (Waste Electrical and Electronic Equipment) Regulations 2005 (S.I. No. 340 of 2005) prior to acceptance at the scrap metal facility.

Class 9	The reception, temporary storage and recovery of used batteries and accumulators where- **(a).** From the 26th September 2008, the treatment and recycling of used batteries and accumulators meets the requirements of Article 12 of directive 2006/66/EC on batteries and accumulators and on waste batteries and accumulators and, **(b).** The annual intake shall not exceed 1,000 tonnes
Class 11	The reception, storage and transfer of waste (other than hazardous waste) for disposal at a facility (other than a landfill facility) where the annual intake does not exceed 7,500 tonnes.

The permitted waste recovery activities, in accordance with the Fourth Schedule of the Waste Management Acts, 1996:

Activity	Description
R4	Recycling reclamation of metals and metal compounds
R5	Recycling/reclamation of other inorganic materials, which includes soil cleaning resulting in recovery of the soil and recycling of inorganic construction materials.
R12	Exchange of waste for submission to any of the operations numbered R1 to R11 (if there is no other R code appropriate this can include preliminary operations prior to recovery including pre-processing such as amongst others; dismantling sorting, crushing, compacting, pelletising, drying, shredding, reconditioning, repackaging, separating blending or mixing prior to submission to any of the operations numbered R1 to R11.
R13	Storage pending any of the operations numbered R1 to R12 (excluding temporary storage (being preliminary storage according to the definition of collection in Section 5(1)), pending collection, on the premises where the waste concerned is produced.

PART 2: CONDITIONS

1.0 SCOPE

1.1 This waste facility permit is issued to **Great White Destruction Ltd of Units 2A-2B Enterprise Centre, Summerhill, Co Meath** for the purpose of waste activity authorisation under the Waste Management (Facility Permit & Registration) Regulations, 2007, as amended for a facility at **Units 2A & 2B Enterprise Centre, Summerhill, Co Meath** to carry on the permitted waste activities listed in Part 1.

1.2 This waste facility permit is valid for a period of 5 years from the date of grant.

1.3 The tonnage accepted at this facility, shall not exceed the limits specified in Appendix A.1.

1.4 The permit holder shall only accept such wastes for recovery/treatment at this facility which are listed in Appendix A.2 of this waste facility permit.

1.5 The area to which the conditions of this waste permit apply is the area within the confines of the red line shown on entitled Site Layout Plan (Ref No. 2020 22 WP101) included with the application subject of this report. Refer to Appendix G for copy of Drawing Ref No. 2020 22.

1.6 The permit holder shall ensure that the facility is compliant with the National Waste Management Plan for a Circular Economy 2024-2030 (as may be revised or replace from time to time) and the National Hazardous Waste Management Plan 2021-2027 (as may be revised or replace from time to time).

1.7 The permit holder shall ensure that, recyclable waste which has been source segregated by the waste producer or collected in source segregated form, shall not be sent for disposal, nor shall it be transported, mixed or handled in a manner so as to make it unsuitable for recycling, recovery or treatment.

1.8 The permit holder shall notify Meath County Council in writing of any proposed changes to the information furnished in the application process or any proposed changes in the activity and shall obtain written approval from Meath County Council prior to these changes taking effect. Should the submission identify a material or significant change in:

(a): The nature, extent or focus of the waste activities;

(b): The nature or extent of any emission;

a waste facility permit review application including the relevant fee may be required before the proposed change can be assessed.

1.9 On completion of waste activities on site the permit holder shall by notice in writing to the Council surrender the facility permit under article 29 of the Regulations.

1.10 Should the permit holder wish to continue to operate after the date of expiry specified in Condition 1.7 above an application to review the facility permit shall be made to the Council in accordance with article 31(1) of the Regulations no later than 60 working days before the date of expiry of the permit.

1.11 The Council may revoke the Waste Facility Permit if it appears to it that:

a) The permit holder or other relevant person, is not, in its reasonable opinion, a fit and proper person to hold a waste facility permit, or
b) Activity being carried out is, or may be, in contravention of the waste facility permit conditions granted by the Local Authority, or
c) Activity is, or may be, in contravention of the Waste Management (Collection Permit) Regulations 2007, as amended
d) Waste facility permit holder, or other relevant person is likely, by the continuation of his or her activities, to cause environmental pollution, or
e) Waste facility permit holder, or other relevant person is participating in, facilitating or otherwise contributing towards the onward movement of waste to unauthorised facilities or unauthorised collectors

2.0 MANAGEMENT OF THE ACTIVITY

2.1 The facility shall be maintained to the satisfaction of Meath County Council, and adequate precautions shall be taken to prevent unauthorised access to the facility.

2.2 The permit holder shall employ or nominate a suitably qualified and experienced facility manager who shall be designated as the person in charge.

2.3 The facility manager or a suitably qualified and experienced deputy shall be present at the facility at all times during its operation or as otherwise required by Meath County Council.

2.4 The facility shall only be operated and waste shall only be accepted at or despatched from the facility between the hours of 07:00 and 17:00, Monday to Friday and between the hours of 07:00 and 12:00 on Saturdays with no deliveries/collections on a Sunday (unless otherwise agreed in writing with Meath County Council. No work (excluding emergency works) shall take place at the facility outside of these hours, unless otherwise approved in writing by Meath County Council.

2.5 The name, address and mobile telephone number of the manager and deputy or deputies shall be supplied to Meath County Council within 4 weeks of the date of grant of this waste facility permit. Meath County Council shall be informed of changes in key staff including the name, address and mobile telephone number of suitably qualified personnel in writing within 10 working days of such change.

2.6 The permit holder shall ensure that employees with responsibilities in waste management and/or pollution control shall be qualified on the basis of appropriate education, training and/or experience. Details of the relevant qualifications shall be maintained and made available to Meath County Council on request.

2.7 The permit holder shall establish and maintain procedures for identifying training needs, and for providing appropriate training. Records of training shall be maintained and made available to Meath County Council on request. ***Where applicable*** - The facility manager and deputy shall successfully complete an appropriate waste management course as approved by Meath County Council.

2.8 The permit holder shall ensure that all staff, employees, lessees and agents, including replacement personnel, are aware of the provisions and conditions of this waste facility permit.

2.9 A copy of this waste facility permit shall be kept on the facility at all times and a copy issued to all relevant personnel whose duties relate to any condition of this permit.

2.10 The permit holder shall ensure that authorised staff of Meath County Council shall have unrestricted access to the facility at all reasonable times on production of their identification, for the purpose of Meath County Council's functions under the Waste Management Act, 1996, including such inspections, monitoring and investigations as are deemed necessary by Meath County Council.

2.11 The permit holder shall have up-to-date written procedures for the following before becoming operational;(*Select relevant procedures.*):

(a) waste inspection
(b) waste acceptance and handling
(c) waste sampling, analysis and characterisation
(d) waste quarantine
(e) waste rejection and notification
(f) corrective action
(g) emergency response procedure (as detailed in Condition 8.3)
(h) invasive species control

2.12 Scavenging shall not be permitted at the facility. There shall be no burning of any waste on site.

2.13 Waste shall only be transferred to authorised waste collectors for onward transport to waste licensed/permitted facilities.

2.14 Waste shall be off-loaded within the confines of the building, no waste is permitted to be stored outside in the yard in waste receptacles or directly on the ground. There shall be no external storage of incoming or processed wastes at the front of the building.

2.15 The permit holder shall ensure that the storage of WEEE shall be in accordance with the minimum requirements set out in the 8th Schedule Technical Requirements in accordance with Article 21 Waste Management (WEEE) Regulations 2014, S.I 149 of 2014 as amended.

2.16 The permit holder shall ensure that waste shipments leaving the facility for export from the state shall comply with the requirements of Regulation (EC) No. 1013/2006, Regulation (EC) No. 1418/2007 & Regulations (EU) 2024/1157 on shipments of waste and the Waste Management (Shipments of Waste) Regulations, S.I. 419 Only single stream uncontaminated wastes on the green list may be exported for recovery using the green list procedure under Regulation 259/93. Co-mingled green list wastes may only be exported for recovery from the facility if the amber list procedure is used.

3.0 NOTIFICATION & RECORD KEEPING

3.1 Waste Register/Records

3.1.1 Unless otherwise specified within this permit or by Meath County Council, all written communications, including reports and notifications related to this permit, shall be:

a) Sent to *Senior Executive Engineer, Environment Department, Meath County Council, Buvinda House, Johnstown, Dublin Road, Navan, Co. Meath* and
b) Submitted in accordance with the reporting frequencies specified in this permit.

3.1.2 The permit holder shall compile and retain records at their principal place of business for a period of not less than 7 years from the date when the records were made, in relation to the activity to which this permit relates.

3.1.3 The permit holder shall not compile information which is false or misleading or incomplete.

3.1.4 All records required shall be legible, be made as soon as reasonably practicable and if amended, be amended in such a way that the original and any subsequent amendments remain legible or are capable of retrieval.

3.1.5 The permit holder shall maintain records of all sampling, analyses, measurements, examinations, calibrations and maintenance carried out in accordance with the requirements of this permit. The permit holder shall record an interpretation of the monitoring results and all other such monitoring which relates to the environmental performance of the facility.

3.1.6 The permit holder shall ensure that a scaled copy of the facility layout plan (minimum scale of 1:500) is retained at the facility, in an easily accessible location, at all times and/or at the principal office of business. The layout plan shall include the following;

(a) Site boundary;
(b) Ordnance survey sheet reference number(s);
(c) Elevation levels (metres) and Ordnance datum;
(d) Dimensions (metres);
(e) Orientation of north point;
(f) Location of drainage infrastructure;
(g) Location of discharge points
(h) Location of monitoring and sampling points; and
(i) Location of silt trap(s)and oil separators

3.1.7 The permit holder shall maintain a register in relation to the activity to which this permit relates, and this register shall be available for inspection by Meath County Council. The register, electronic, if possible, shall detail the following: (See Appendix B, Table B.1, for example table):

a) **Arriving at facility: -** (See Appendix B, Table B.1, for example table)
   (i) Dates and times of each waste consignment delivered to the facility,
   (ii) Name of the carrier, their vehicle registration and waste collection permit number (as applicable);
   (iii) Origin of waste delivered; (i.e. Household /Commercial /Industrial/ C&D/ Waste Management Facility);
   (iv) Details of visual inspection;
   (v) Quantities in tonnes, LoW[1] code and description of each waste consignment received at the facility;
   (vi) Name of person who checked the load

b) **Departing from facility: -**
   (i) Dates and times of all waste moving off site;
   (ii) Name of the carrier, their vehicle registration and waste collection permit number;
   (iii) Quantities in Tonnes, LoW code and description of waste streams consigned for onward transport from the facility;
   (iv) Details of the facility, including permit/licence number, which is being used to receive such waste;
   (v) Quantities and composition of wastes rejected at the facility and the facility to which they were removed.
   (vi) Quantity and detailed description of materials dispatched from the facility, having attained End-of-Waste status, following treatment at the facility.

3.1.8 The permit holder shall maintain a register, electronic if possible, of all inspections and maintenance work carried on the site and this register shall be available for inspection by Meath County Council.

3.2 Incident Reporting & Complaints Register

3.2.1 The permit holder shall notify Meath County Council by telephone at **046-9097200**, or email environment@meathcoco.ie as soon as is practicable and in any case not later than 10.00 am the following working day, of any incident which occurs as a result of an activity at the facility that:

[1] (by List of Wastes (LoW)(s) and description(s) pursuant to Commission Decision of 18 December 2014, amending Decision 2000/532/EC on the list of waste pursuant to Directive 2008/98/EC of the European parliament and of the Council (2014/955/EEC) [referred to hereafter as 'The List of Waste (LoW)'] and Commission Regulation (EU) No 1357/2014 of 18 December 2014, replacing Annex III to Directive 2008/98/EC of the European Parliament and of the Council on waste and repealing certain Directives'

a) Has the potential for pollution of surface water or ground water or;
b) Poses an environmental threat to air or land or;
c) Requires an emergency response by Meath County Council or other state agency.

In the event of an incident which has the potential for pollution of surface water, the permit holder shall notify Inland Fisheries Ireland as soon as is practicable, and in any case not later than 10.00 am the following working day.

3.2.2 Full details of the incident shall be recorded in a register (refer to Appendix C, Table C.1, for example table) and details forwarded in writing to Meath County Council within 5 working days. The permit holder shall include as part of this notification:

(a) The date and time of incident, or when incident was noticed.
(b) Details of the incident and the causes or potential causes of it.
(c) An evaluation of environmental pollution caused, if any.
(d) Actions taken to minimise the effect on the environment.
(e) Steps taken to avoid reoccurrence.
(f) Details of any site investigations instigated by the permit holder.
(g) Any other remedial action; and
(h) Name of responsible person managing the incident.

3.2.3 The permit holder shall maintain on the site, a register, electronic, if possible, of all complaints received relating to the operation of the activity (Refer to Appendix D, Table D.1, for example table). Each such complaint entry in the register shall give details of the following:

(a) Time and date of the complaint;
(b) The name of the complainant;
(c) Details of the nature of the complaint;
(d) Actions taken to deal with the complaint, and the results of such actions;
(e) The response made to each complainant.

3.2.4 The permit holder shall notify Meath County Council, in writing, within 5 working days of:

(a) The imposition of any requirement on the permit holder by order under the Waste Management Act 1996, or
(b) Any conviction of the permit holder for an offence prescribed under the Waste Management Act 1996.

3.3 Annual Report

3.3.1 The permit holder shall submit to Offaly County Council as the National Waste Collection Permit Office (NWCPO), an Annual Report (AR). The completed report shall be submitted via the online web portal (https://ar.nwcpo.ie/) no later than the 28th February each year, or as

specified by NWCPO. The completed report shall contain summary information relating to waste activities in the preceding calendar year, or part thereof as the case may be, as set out in Condition 3.3.2.

3.3.2 The on-line AR, shall include as a minimum the following information and shall be prepared in accordance with any relevant guidelines issued by the NWCPO and/or Meath County Council:

A NIL return applies when in the relevant calendar year

- NO Waste was accepted onto the site and
- NO Waste was processed on site and
- NO Waste was removed from site

In these circumstances a NIL return must be reported as per the relevant guidelines referred to above.

a) Waste In:

For each carrier/waste collector who delivered waste to the facility, in the preceding calendar year, the following summary details are required:

(i) carrier/waste collection permit holder details;
(ii) Waste code (LoW) [2];
(iii) Quantity (in tonnes);
(iv) Code of activity.
(v) Each waste carries shall be issued with a receipt as outlined in Appendix G.

b) Waste Out:

In relation to waste removed from the facility, in the preceding calendar year, the following summary details are required:

(i) Waste collection permit holder details;
(ii) Waste code (LoW)[3];
(iii) Quantity (in tonnes);
(iv) Destination facility details;
(v) Quantity and description of materials dispatched from the facility, under end-of-waste status.

c) Waste On Site:

Record the opening and closing stock balance (tonnes) for each waste code (LoW), for the reporting year.

d) Remaining Capacity

Record and report the remaining permitted capacity in tonnes, as at the 31st December of the reporting year.

[2] Further details are required for LoW 20 03 01, 16 01 03, 16 01 04*, 16 01 06 & sewage sludge codes
[3] Further details are required for LoW 20 03 01, 16 01 03, 16 01 04*, 16 01 06 & sewage sludge codes

e) Supporting Documentation - where applicable

(i) The management and staffing structure of the site.

(ii) Any court order or conviction under the Act.

(iii) Summary of any loads rejected at the facility, as per Condition 3.1.7;

(iv) Summary of reportable incidents during the reporting year and corrective actions taken, as per Condition 3.2.2;

(v) Summary of complaints received during the reporting year and corrective actions taken, as per Condition 3.2.3;

(vi) Where relevant for the reporting year in question, details of bund testing, as per Condition 4.2.4;

(vii) A copy of the signed annual maintenance contract for the oil separator(s) at the facility as per Condition 4.3.5;

(viii) Details of environmental monitoring undertaken at the facility as per Condition 6;

(ix) Where relevant, details of the Environmental Liability Risk Assessment (ELRA) as per Condition 7.1.2;

(x) Details of the pest controls as per Condition 7.5.1;

(xi) Details of the fire risk assessment for the facility, as per Condition 8.4;

(xii) Copy of the public liability insurance policy in place as per Condition 9.2.3;

(xiii) Where relevant, copy of the Environmental Liabilities Insurance policy as per Condition 9.2.4;

(xiv) Details of the review of the closure, restoration and aftercare management plan (CRAMP), as per Condition 10.1.1.

4.0 SITE ACCESS & INFRASTRUCTURE

4.1 Facility Notice Board

4.1.1 Prior to the facility becoming operational, the permit holder shall provide and maintain a Facility Notice Board at the facility, so that it is legible to persons outside the main entrance to the facility. The minimum dimensions of the board shall be 1200 mm by 750 mm.
The board shall clearly show:

(a) The name and telephone number of the facility;
(b) The normal hours of opening;
(c) The name of the permit holder;
(d) An emergency out of hours contact telephone number;
(e) The most up-to-date WFP Register Number, as specified on the cover page of this permit; and
(f) Where environmental information relating to the facility can be obtained.

4.1.2 At the entrance to the facility, the permit holder shall display a plan of the facility clearly identifying the location of the waste drop-off and storage areas. The plan shall be displayed on a durable material and shall be replaced as material changes are made.

4.2 Tank, Container & Drum storage area

4.2.1 All tank, container and drum storage areas shall be rendered impervious to the materials stored therein. Bunds shall be designed having regard to EPA guidelines *Storage and Transfer of Materials for Scheduled Activities (2004).*

4.2.2 All tank and drum storage areas shall, as a minimum, be bunded, either locally or remotely, to a volume not less than the greater of the following:
a) 110% of the capacity of the largest tank or drum within the bunded area; or
b) 25% of the total volume of substance which could be stored within the bunded area.
The height of the bund for any drum storage area shall be not less than 300mm.

4.2.3 The permit holder shall ensure that all drum bunded areas are securely covered so that rainwater is excluded from entering the area unless otherwise agreed in writing with Meath Council.

4.2.4 All drainage from bunded areas shall be treated as hazardous waste unless it can be demonstrated to be otherwise. All drainage from bunded areas shall be diverted for collection and safe disposal by an appropriately authorised waste collector.

4.2.5 All inlets, outlets, vent pipes, valves and gauges shall be within the bunded area.

4.2.6 All tanks, containers and drums shall be labelled to clearly indicate their contents and capacity.

4.2.7 The permit holder shall ensure that refuelling of site vehicles is carried out at a designated point on an impervious concrete slab from which surface water drains through an oil interceptor.

4.3 Facility Security

4.3.1 The permit holder shall ensure adequate security by erecting and maintaining fencing and gates at the facility.

4.3.2 The permit holder shall ensure that all entrances to the facility shall be gated and locked, when there is no facility manager or designated deputy manager present at the facility. Unless they are trained, qualified and experienced (in accordance with Condition 2 of this waste facility permit), drivers of waste delivery vehicles are not deemed facility supervisory staff.

4.3.3 The permit holder shall remedy any defect in the entrances and/or fencing or wall as follows:

a) A temporary repair shall be made by the end of the working day; and
b) A repair to the standard of the original gates and/or fencing or wall, shall be undertaken within three working days.

4.4 Facility Roads & Surfaces

4.4.1 The permit holder shall provide sufficient hardcore material or better at the site entrance to allow easy access to the site by vehicles and reduce / avoid damage to the public road at the site entrance. Any debris caused by vehicles entering or leaving the facility shall be removed without delay.

4.4.2 Effective or adequate site roads and surfacing shall be provided and maintained to ensure the safe and nuisance free movement of vehicles within the facility.

4.4.3 Any defects in facility roads or surfaces shall be remedied within five working days.

4.5 Facility Office

4.5.1 The permit holder shall provide and maintain an office at the facility. The office shall be constructed and maintained in a manner suitable for the processing and storage of documentation.

4.5.2 The permit holder shall provide and maintain a working telephone and a method for electronic transfer of information at the facility.

4.6 Waste Inspection and Quarantine

4.6.1 A waste inspection area(s) and waste quarantine area(s) shall be provided and maintained at the facility, and agreed by the Enforcement Officer, prior to the importation of any waste to the facility.

4.6.2 These areas shall be constructed and maintained in a manner suitable, and be of a size appropriate, for the inspection of waste and subsequent quarantine if required.

4.6.3 The waste inspection area(s) and waste quarantine area(s) shall be clearly identified, segregated from each other, protected against spillage and polluting material run-off and shall not be used for any other purpose other than that designated.

4.6.4 Waste shall be stored under appropriate conditions in the quarantine area to avoid putrefaction, odour generation, the attraction of vermin and any other nuisance or objectionable condition.

4.6.5 The quarantine area shall include a skip(s) for the storage of rejected waste.

4.7 Storm Water

4.7.1 The permit holder shall ensure that no surface water generated on site flows onto the public road or onto adjoining properties.

4.7.2 The permit holder shall ensure that storm water gutters are maintained in good condition and all uncontaminated storm water is re-used where practicable or diverted to a separate soak-way/drainage system.

4.7.3 The permit holder shall ensure that no alterations to the drainage system at the site shall be undertaken without prior written approval of Meath County Council.

4.7.4 The permit holder shall incorporate an inspection chamber with a sump into the surface water drainage system. The sump shall be of a minimum size of 500mm square and 400mm deep.

4.7.5 No trade effluent shall be discharged to waters/sewers unless in accordance with a licence issued under the Water Pollution Act 1977 as amended.

4.8 Waste Handling, Ventilation and Processing Plant

4.8.1 Items of plant deemed critical to the efficient and adequate processing of waste at the facility (including inter alia waste loading vehicles and ejector trailers) shall be provided on the following basis:

a) 100% duty capacity;
b) 20% standby capacity available on a routine basis; and
c) Provision of contingency arrangements and/or back up and spares in the case of breakdown of critical equipment.

4.8.2 Prior to the facility becoming operational, the permit holder shall provide a report for the agreement of Meath County Council detailing the duty and standby capacity in tonnes per

day, of all waste handling and processing equipment to be used at the facility. These capacities shall be based on the permitted waste intake, as per Appendix A.

4.8.3 The quantity of waste to be accepted at the facility on a daily basis shall not exceed the duty capacity of the equipment at the facility. Any exceedance of this intake shall be treated as an incident, in accordance with Condition 3.2.

4.8.4 A maintenance schedule shall be maintained for all waste handling and processing equipment used at the facility and a record of all maintenance undertaken shall be recorded. The schedule and records shall be made available to Meath County Council on request.

5.0 WASTE ACCEPTANCE & HANDLING

5.1 Waste Acceptance

5.1.1 The permit holder shall ensure that all vehicles delivering waste to and removing waste from the facility are securely covered.

5.1.2 Waste arriving at the facility shall be inspected at the point of entry to the facility and subject to this inspection, weighed, documented and directed to the appropriate area/tipping point. Each load of waste arriving at the appropriate area/tipping point, shall be inspected upon tipping. Only after such inspections shall the waste be processed for recovery or subsequent disposal off-site.

5.1.3 Any waste deemed unsuitable for acceptance or handling at the facility and/or in contravention of this permit shall be immediately separated and removed from the facility at the earliest possible time. Such waste shall be recovered or disposed of at an alternative facility with appropriate waste authorisation. Temporary storage of such wastes shall be in the designated waste quarantine area (Condition 4.7).

5.1.4 All waste arriving at the facility shall be brought by Vehicles owned or operated by Great White Destruction Ltd & subject to a visual inspection. Material other than those permitted under condition 1.4 shall be removed immediately from the facility. Such waste shall be disposed of (or recovered) at an alternative facility with an appropriate authorisation.

6.0 ENVIRONMENTAL MONITORING

6.1 Environmental Monitoring

6.1.1 The permit holder shall carry out such monitoring of surface water /ground water/ noise/ odour/dust, at such locations, frequencies, parameters and using the method/technique, as set out in Appendix E, unless otherwise agreed with Meath County Council.

6.1.2 The permit holder shall, at his/her own expense, carry out such further investigations and monitoring of the facility as required by Meath County Council.

6.1.3 Unless otherwise specified by the waste facility permit, environmental monitoring shall commence no later than **1 month** after the date of grant of this permit.

6.1.4 Sampling, monitoring and analytical equipment shall be operated, maintained and calibrated in accordance with the manufacturer's instructions to ensure that all monitoring results accurately reflect any emission, discharge or environmental parameter.

6.1.5 All sampling, monitoring and analyses shall be carried out by appropriately competent persons, and all analyses shall be carried out by an appropriately accredited laboratory.

6.1.6 The Permit Holder shall clearly label and provide safe and permanent access to all on-site sampling and monitoring points, and to off-site points, as required by Meath County Council.

6.2 Discharge to Surface Water

6.2.1 Checks of all surface water discharge point(s) at the facility shall be carried out weekly. These inspections shall be recorded, and copies of these completed records shall be made available to Meath County Council on request.

6.3 Noise

6.3.1 The pre-existing ambient noise level shall be determined by the permit holder, prior to commencement of the operational phase of the facility.

6.3.2 The permit holder shall carry out the activity in a manner that ensures emissions from the activity do not result in the production of unreasonable noise, vibrations, or sound at any Noise Sensitive Locations (NSLs) or beyond the site boundary.

7.0 NUISANCES, EMISSIONS & ENVIRONMENTAL IMPACT

7.1 Environmental Protection

7.1.1 The only emissions to any media allowed from the facility are those provided for in Appendix F: *Emission Limits* of this permit or a discharge licence issued by Meath County Council in accordance with the Water Pollution Act 1977, as amended. Where applicable under Environmental Protection: Refer to *EPA Approach to Environmental Liabilities and Financial Provision (2019)*

7.1.2 The permit holder shall arrange for the completion, by an independent and appropriate qualified 3rd party, of a comprehensive and fully costed Environmental Liability Risk Assessment (ELRA) to address the liabilities from the past and present activities. The ELRA shall include those liabilities and costs associated with closure of the site or part thereof. **A report on the ELRA shall be submitted to Meath County Council for agreement within 6 months of the date of grant of this permit.** The ELRA shall be reviewed as necessary to reflect any significant change on site, and in any case every three years following initial agreement. The results of the review shall be notified as part of the annual report, for the relevant reporting year.

7.1.3 The permit holder shall have regard to the EPA Guidance documents - "*Guidance on assessing and costing environmental liabilities*" (EPA, 2014) and "*Guidance on Financial Provision for Environmental Liabilities*" (EPA, 2015) when implementing condition 7.1.2.

7.2 Noise/Odour/Dust/Nuisances

7.2.1 The permit holder shall take adequate precautions, as agreed with Meath County Council, to prevent noise, odours, fumes, dust, mud, grit, untidiness and other nuisances that would result in a significant impairment of, or a significant interference with amenities, or the environment beyond the facility boundary, from arising during the course of the waste activities at the facility. If unacceptable levels occur, the permit holder shall abide by Meath County Council abatement requirements, which may include immediate cessation of operations.

7.2.2 Noise levels emanating from the waste facility when measured at the boundaries of the facility shall not exceed ban LAr,T value and LA eq of 55 dB (A) during the period 7.00 am – 7pm Monday to Friday and from 8.00 am – 12 pm on Saturdays" LAr,T is being required to

take account for tonal characteristics. The Council reserves the right to instruct the permit holder, to the immediate cessation of all operation works, at the facility, until such time as it is proven to the Council, that the exceedance in the noise levels has dissipated, and the problem/s has been resolved. The operations / works at the facility can only recommence, on the written instructions of Meath County Council.

7.2.3 The permit holder shall not allow any over-spill of waste outside the site perimeter/boundary, as outlined on the site plan entitled submitted with the review permit application.

7.2.4 In dry weather, site roads and any other areas used by vehicles shall be sprayed with water as and when required to minimise airborne dust nuisance.

7.3 Litter

7.3.1 All loose litter or other waste, placed on or in the vicinity of the facility, other than in accordance with the requirements of this permit, shall be removed immediately and in any event by the next working day after such waste is discovered.

7.4 Pests

7.4.1 The permit holder shall ensure sufficient and continuous pest controls are established and maintained. Records of same shall be maintained on site and shall be made available to Meath County Council on request and submitted as part of the annual report.

8.0 CONTINGENCY ARRANGEMENTS

8.1 The permit holder shall have in storage an adequate supply of containment booms and/or suitable absorbent material to contain and absorb any spillage, such as oil spill, or similar incident at the facility. Once used the absorbents shall be replaced and the absorbent material shall be disposed of appropriately, and records maintained. Any spillages shall be treated as an incident, in accordance with Condition 3.2.

8.2 Adequate fire extinguishers and emergency response equipment shall be maintained at the facility following consultation with the Fire Service Department. A fire at the facility shall be treated, as an emergency and immediate action shall be taken to extinguish it and notify the appropriate authorities. Any fire shall be treated as an incident, in accordance with Condition 3.2.

8.3 The permit holder shall carry out a risk assessment and ensure that an Emergency Response Procedure (ERP) is in place, which shall address any emergency which may arise on-site. This procedure shall be communicated to all site staff and include provision for minimising the effects of any emergency on the environment. In particular the procedure shall include details of:

a). actions to be taken in the event of an incident.
b). firefighting and water retention facilities.
c). warning systems;
d). assembly points.
e). responsible persons, training and equipment requirements and relevant bodies to be notified following the incident.

An ERP was submitted to Meath County Council as part of the application process and will be held on file for duration of the permit.

8.4 The permit holder shall arrange, within <u>three months</u> of the date of grant of this permit **and every three years thereafter** or as directed by Meath County Council, for the completion of a fire risk assessment and report for the facility, by a suitably qualified person. The assessment shall examine all relevant factors on site that impinge on fire risk and prevention. The assessment shall have regard to the *Guidance Note: Fire Safety at Non-Hazardous Waste Transfer Stations* (EPA 2013). Any recommendations in the fire risk assessment report shall be implemented by the permit holder. The results of the assessment shall be submitted as part of the annual report, for the relevant reporting year.

9.0 CHARGES & FINANCIAL PROVISIONS

9.1 Fees

9.1.1 Prior to the commencement of operations, the permit holder shall lodge with Meath County Council a cash deposit of **€5,000** as a security for the satisfactory compliance by the permit holder with the terms and conditions attached to this permit. In the event of non-compliance by the permit holder with any terms or conditions attached to this permit, the Council shall be empowered to apply the said funds or part thereof for the satisfactory compliance with the terms and conditions attached to this permit. On surrender of the waste facility permit, the Council may decide that the cash deposit or part thereof, shall be maintained in place for such a period until the permit holder has fully complied with the terms and conditions attached to the waste facility permit, to the satisfaction of the Council, or may be released to the permit holder.

9.1.2 The permit holder shall pay an annual contribution in the sum of **€1,500** to Meath County Council towards the cost of inspecting, monitoring, auditing, enforcing or otherwise performing any function in relation to the permitted activities. The permit holder shall pay this amount annually, not later than January 31st of any given year. This monitoring fee will be updated annually in accordance with Table 5 of the All Items Index (base at November 1975 = 100) published by the Central Statistics Office. The Council will notify the updated amount to the permit holder.

9.1.3 In the event that the frequency or extent of monitoring or other functions carried out by Meath County Council needs to be increased for whatever reason, the permit holder shall contribute such sums as are determined by Meath County Council to defray costs. These costs shall be paid in full within 20 working days of receipt of notification from the Meath County Council of the costs incurred.

9.2 Financial Provisions

9.2.1 The permit holder shall ensure that all insurance policies shall be extended to indemnify Meath County Council.

9.2.2 Without prejudice to the foregoing, the minimum level of indemnity to be maintained by the permit holder shall be to the value of **€6,500,000** for public liability insurance including cover for sudden and unforeseen pollution.

9.2.3 A copy of the insurance shall be furnished to Meath County Council prior to commencement of activity, and thereafter it shall be submitted every year as part of the annual report.

9.2.4 The permit holder shall ensure that sufficient financial resources are available to cover unknown liabilities that may occur during the operating life of the facility. The level of financial provision for unknown environmental liabilities shall be based on the results of the Environmental Liability Risk Assessment (ERLA) to be undertaken in accordance with Condition 7.1.2. The financial provision shall be in the form of adequate environmental liabilities insurance and a copy of the insurance policy shall be submitted within one month of the approval of the ELRA and thereafter it shall be submitted every year as part of the annual report.

Refer to *EPA Approach to Environmental Liabilities and Financial Provision (2019)*

https://www.epa.ie/our-services/compliance--enforcement/industry-and-waste-management/financial-provision-for-environmental-liabilities/

10.0 RESTORATION & AFTERCARE

10.1 Closure, Restoration & Aftercare Management Plan (CRAMP)

10.1.1 The permit holder shall prepare, to the satisfaction of Meath County Council, a fully detailed and costed CRAMP for the site or part thereof. This plan shall be prepared by a suitably qualified person, as approved by Meath County Council and:

(i) Have regard to the *Guidance on Assessing and Costing Environmental Liabilities* (EPA 2014);

(ii) Be submitted to Meath County Council for agreement **within six months** of the date of grant of the waste facility permit;

(iii) Be reviewed annually and proposed amendments shall be submitted to Meath County Council for its agreement. The results of the review shall be submitted as part of the annual report.

10.1.2 The CRAMP shall include, as a minimum, the following:

a) A scope statement for the plan;

b) The criteria that define the successful decommissioning and aftercare of the activity or part thereof, which ensures minimum impact on the environment;

c) A programme to achieve the stated criteria;

d) Where relevant, a test programme, (e.g. trial holes at a C&D site,) to demonstrate the successful implementation of the decommissioning and aftercare plan.

e) Details of the costings for the plan and financial provisions to underwrite these costs.

f) A proposed final levels contour drawing if applicable ;

g) Proposals to ensure satisfactory drainage of the imported inert material and to ensure that ponding does not occur in the topsoil layer.

10.1.3 On cessation of waste activities at the facility, the permit holder shall apply in writing to the Council to surrender the permit as prescribed in condition 1.9. In the event of failure to surrender the waste facility permit Meath County Council will assume the continuance of the Waste activity until the date of expiration of the Waste Facility Permit and the permit holder will be charged accordingly.

11.0 CHANGES TO PERMIT HOLDER STATUS & CESSATION OF WASTE ACTIVITIES

11.1 Changes to permit holder status:

11.1.1 The permit holder shall notify Meath County Council in writing within 14 working days of the occurrence of the following matters, except where such disclosure is prohibited by Stock Exchange rules:

Where the Permit Holder is a registered company:

a) any change in the operator's trading name, registered name or registered office address;

b) any change to particulars of the operator's ultimate holding company (including details of an ultimate holding company where an operator has become a subsidiary); and

c) any steps taken with a view to the operator going into administration, entering into a company voluntary arrangement or being wound up.

Where the Permit Holder is a corporate body other than a registered company:

a) any change in the operator's name or address; and

b) any steps taken with a view to the dissolution of the operator.

In any other case:

a) any steps taken with a view to the operator, or any one of them, going into bankruptcy, entering into a composition or arrangement with creditors, or, in the case of them being in a partnership, dissolving the partnership.

11.2 Cessation of waste activities:

11.2.1 Following termination or planned cessation, for a period greater than six months, of use or involvement of all or part of the permitted site, the permit holder shall, to the satisfaction of Meath County Council, decommission, render safe or remove for disposal/recovery any soil, subsoil, buildings, plant or equipment, or any waste, materials or substances or other matter contained therein or thereon, that may result in environmental pollution. The permit holder shall carry out such tests or investigation or submit certification, as requested by Meath County Council, to confirm there is no risk to the environment.

11.2.2 A final validation report to include a certificate of completion for the decommissioning and aftercare plan, for all or part of the permitted site as necessary, shall be prepared by a suitably

qualified person as agreed with Meath County Council, and submitted to Meath County Council within three months of execution of the plan.

11.2.3 Following cessation of activities on site, where required, the permit holder shall forward to Meath County Council, information demonstrating compliance with any of the conditions attached to this permit, and details of any court order or conviction under the Act.

APPENDICES

APPENDIX A:

APPENDIX A.1. – PERMITTED WASTE TONNAGE

The total maximum annual permitted tonnage shall not exceed **6,500 tonnes per annum** at this facility.

APPENDIX A.2 – WASTE ACCEPTANCE

Only the wastes as specified in Table A.2.1 are acceptable for recovery/treatment at this facility unless otherwise agreed by with Meath County Council.

Table A.2:1 – Waste Categories

LoW Code	*LoW Waste Description*	*Quantity Tonnes (applicant Specify WFP Application)*
08 03 17	Waste Printing toner containing dangerous substances	0.5
08 03 18	Waste Printing toner other than those mentioned in 08 03 17	0.5
09 01 08	Photographic film and paper free of silver and silver compounds	5
15 01 01	Paper and cardboard packaging	1000
15 01 02	Plastic packaging	20
15 01 03	Wooden Packaging	12
15 01 04	Metallic Packaging	0.5
15 01 05	Composite packaging	0.5
15 01 06	Mixed packaging	1
15 01 07	Glass packaging	0.5
16 02 14	discarded equipment other than those mentioned in 16 02 09 to 16 02 13	2
16 02 16	components removed from discarded equipment other than those mentioned in 16 02 15	150
16 06 01*	Lead batteries	1.5
16 06 02*	Ni-Cd batteries	0.5
16 06 03*	mercury-containing batteries (except 16 06 03)	0.5
16 06 04	Alkaline batteries	0.5
16 06 05	Other batteries and accumulators	0.5
17 04 02	aluminium	15
17 04 05	iron and steel	1
17 04 07	mixed metals	15
17 04 11	cables other than those mentioned in 17 04 10	1
19 12 01	paper and cardboard	500
19 12 02	ferrous metal	25

19 12 03	non-ferrous metal	16
19 12 04	plastic and rubber	1
20 01 01	Paper & Cardboard	4500
20 01 02	Glass	0.5
20 01 10	clothes	3
20 01 11	Textiles	5
20 01 33*	batteries and accumulators included in 16 06 01, 16 06 02 or 16 06 03 and unsorted batteries and accumulators containing these batteries	0.5
20 01 34	batteries and accumulators other than those mentioned in 20 01 33	1
20 01 36	Discarded electrical and electronic and electronic equipment other than those mentioned in 20 01 21, 20 01 23, & 20 01 35	140
20 01 38	Wood other than those mentioned in 20 01 37	3
20 01 39	Plastics	1
20 01 40	Metals	35
20 01 99	other fractions not otherwise specified	1.5
20 03 01	mixed municipal waste	40
TOTAL		**6,500.50**

Appendix B- Waste Register

Table B.1: Condition 3.1.7- Waste Register – Arriving at Facility

Date	Time	Carrier Details, (Name,Vehicle Reg. & WCP No.)	Origin of waste delivered	LoW Code	Waste Description	Details of visual inspection (soil & stone)	Tonnage IN	Quantities and composition of wastes rejected	Tonnage OUT	Destination Facility (including authorisation No.)	Name of the Load Checker	Tonnage End-of-Waste OUT

Table B.2: Condition 3.1.7- Waste Register - Departing from facility

Date	Time	Carrier Details, (Name, Vehicle Reg. & WCP No.)	LoW Entry (Code)	LoW Entry (Description)	Tonnage OUT	Details of visual inspection	Quantities and composition of wastes rejected	Destination Facility (including authorisation No.)	Name of the Load Checker	Tonnage End-of-Waste OUT

Appendix C – Incident Register

Table C. 1 - Condition 3.2.2: Register of Incident which has Potential to Cause Environmental Pollution

Date of Incident	Date notified to LA Name Council	Time of Incident	Details of Incident and the causes/potential causes	Evaluation of Environmental Pollution	Actions taken to Minimise the Effect on the Environment	Steps Taken to Avoid Reoccurrence	Details of any site investigations instigated by the permit holder	Other remedial action undertaken or to be undertaken, including details of preventative measures taken.

Appendix D – Complaints Register

Table D. 1 - Condition 3.2.3: Register of Complaints

Date of Complaint	Time of Complaint	Name of Complainant	Details of Complaint	Actions Taken	Result(s) of action taken	Response to Complainant

APPENDIX E - ENVIRONMENTAL MONITORING

Condition 6.1.1: Environmental Monitoring

Monitoring Locations

Monitoring locations shall be those as set out in Table E.1.

Table E.1 Monitoring Locations

Parameter	Location
Surface Water	Weekly
Noise	As Required
Odour	Not applicable
Dust	Not applicable

Note 1: All analyses shall be carried out by an appropriately accredited laboratory.

Noise Monitoring

Table E.2: Noise Monitoring Frequency

Parameter	Monitoring Frequency	Method
During the operational stage the noise levels at noise sensitive receptors shall not exceed 55 dB(A) during the period 08.00 – 18.00 hrs Monday to Friday and from 08.00 – 14.00 hrs on Saturdays" LAr,T is being required to take account for tonal characteristics.	As Requested by LA	Note 1

Note 1: The survey programme shall be undertaken in accordance with the methodology specified in the EPA *Guidance Note for Noise: Licence Applications, Surveys and Assessments in Relation to Scheduled Activities (NG4)* (January 2016).

Surface Water – Drains & Discharge Points

Table E.3:

Parameter	Monitoring Frequency	Method
Visual	Weekly	Visual Check

Nuisances (including but not limited to vermin, bords, floes, mud, dust, noise, odour, litter, fumes, untidiness, grit and other nuisances)

Table E. 4

Parameter	Monitoring Frequency	Method
Nuisances	Daily	Visual Check

Note 2: Checks shall be recorded daily, and records maintained onsite for inspection.

Appendix F - ARTICLE 21 WASTE MANAGEMENT (WEEE) REGULATIONS

EIGHTH SCHEDULE
TECHNICAL REQUIREMENTS IN ACCORDANCE WITH ARTICLE 21 WASTE MANAGEMENT (WEEE) REGULATIONS, S.I. NO. 149 OF 2014

1. Sites for storage (including temporary storage) of WASTE ELECTRICAL AND ELECTRONIC EQUIPMENT prior to their treatment (without prejudice to the requirements of Council Directive 1999/31/EC):
   - Impermeable surfaces for appropriate areas with the provision of spillage collection facilities and, where appropriate, decanters and cleanser-degreasers,
   - weatherproof covering for appropriate areas.

2. Sites for treatment of WASTE ELECTRICAL AND ELECTRONIC EQUIPMENT:
   - balances to measure the weight of the treated waste,
   - Impermeable surfaces and waterproof covering for appropriate areas with the provision of spillage collection facilities and, where appropriate, decanters and cleanser-degreasers,
   - appropriate storage for disassembled spare parts,
   - appropriate containers for storage of batteries, PCBs/ PCTs containing capacitors and other hazardous waste such as radioactive waste,
   - Equipment for the treatment of water in compliance with health and environmental Regulations.

APPENDIX G - SITE MAPS




A
B
C
D
E
F
LEGEND
FRONT (SOUTH FACING) ELEVATION
REAR (NORTH FACING) ELEVATION
UNIT 2A
UNIT 2B
SECTION AA
DRAWING
WASTE FACILITY PERMIT


LEGEND
SIDE (EAST FACING) ELEVATION
SCALE 1:100
REAR (NORTH FACING) ELEVATION SPRINKLER STORAGE TANK, PUMP HOUSE AND ESB SUB STATION
SCALE 1:100
FRONT (SOUTH FACING) ELEVATION SPRINKLER PUMP HOUSE AND ESB SUB STATION SCALE 1:100
SIDE (WEST FACING) ELEVATION
SCALE 1:100
DRAWING
WASTE FACILITY PERMIT
SHAY SCANLON
ARCHITECT



GROUND FLOOR PLAN

Meath County Council - Approved Officers Order

Ref Number AO 30951/2025 **(Environment)**

Order Subject Application for a Waste Facility Permit under Article 18(1) of the Waste Management (Facility Permit & Registration) Regulations S.I. No.821 of 2007 amended by the Waste Management (Facility Permit Registration) (Amendment) Regulations S.I. No. 86 of 2008 & Waste Management (Facility Permit & Registration) (Amendment) Regulations 2014, S.I. 320 of 2014. Applicant: Great White Destruction, Units 2A-2B Enterprise Centre, Summerhill, Co. Meath, Ref no: WFP/MH/20-0008-02

Submitted Details (A)Complete Application dated 02/09/2025 (B)Report & Recommendation by Helen Smith, Executive Scientist dated 20/11/2025 & endorsed by Shane Carroll, Senior Executive Engineer dated 24/11/2025 (C)Delegation of Function Order No. CS CEO 6327/2025 to Kitty Foyle, Senior Executive Officer, Environment & Water Services, Meath County Council

Order Details By virtue of the powers conferred on me, I hereby order that a Waste Facility Permit is granted in accordance with Article 18(1) of the Waste Management (Facility Permit & Registration Regulations) S.I. No. 821 of 2007 as amended The waste recovery operations are in accordance with the third schedule of the Waste Management Act 1996. (R4) Recycling reclamation of metals and metal compounds, (R5) Recycling/reclamation of other inorganic materials, which includes soil cleaning resulting in recovery of the soil and recycling of inorganic construction materials. (R12) Exchange of waste for submission to any of the operations numbered R1 to R11 (if there is no other R code appropriate this can include preliminary operations prior to recovery including pre-processing such as amongst others; dismantling sorting, crushing, compacting, pelletising, drying, shredding, reconditioning, repackaging, separating blending or mixing prior to submission to any of the operations numbered R1 to R11. (R13) Storage pending any of the operations numbered R1 to R12 (excluding temporary storage (being preliminary storage according to the definition of collection in Section 5(1)), pending collection, on the premises where the waste concerned is produced.
To: Great White Destruction, Units 2A-2B Enterprise Centre, Summerhill. Location of proposed development: Great White Destruction, Units 2A-2B Enterprise Centre, Summerhill. Subject to 11 Conditions as set out on the Schedule attached hereto.

Signed By

Approved Officer - AO 30951/2025 (Environment)
Pursuant to a Delegation Order under Section 154 of the Local Government Act 2001 as amended by Local Government Act 2014

Date Signed 24/11/2025

AO 30951/2025 (Environment)

Created By:	Team Environment Admin (Joanne Sheridan)	**Checked By:**	**AO 30951/2025 (Environment)**	**Checked By Position:**	**AO 30951/2025 (Environment)**